BILL OF QUANTITIES - 3 BEDROOM BUNGALOW, LEKKI

Item	Description	Unit	Qty	Rate (N)	Amount (N)
	SUBSTRUCTURE				
A	Excavate foundation trench	m3	24	4,500	108,000
B	Concrete 1:2:4 in strip foundation	m3	12	85,000	1,020,000
C	Labour: setting out and blinding	item	1	60,000	60,000
	Sub-total carried to summary				1,188,000
	SUPERSTRUCTURE				
D	225mm sandcrete blocks	nr	1800	650	1,170,000
E	Bricklayer workmanship to block walls	m2	220	1,500	330,000
F	Y12 reinforcement bars	tonnes	1.5	1,100,000	1,650,000
	GRAND TOTAL				4,338,000